

ITER an unprecedented international collaboration in energy research

Carlos Alejandre (MEC, Spain)
for the ITER International and Participant Teams



European Conference on Infrastructures (ESFRI)
Nottingham, 6 December 2005

ITER

Outline


- Introduction: Fusion Results
- Technical and Organisational Preparations
- Negotiations Status
- Risk Assessment
- Conclusions

Acknowledgements
S. Shimomura, B. Spears,
P. Barabaschi and ITER team
J. Doncel (MEC)

ITER

Fusion Power Results

- Experiments in JET and TFTR have initiated the study of DT plasmas with significant fusion power: best JET results correspond to a fusion power production of 16MW
- α -particle heating amounted to ~15% of the input power to the plasma




ITER

Fusion Results


ITER

Globally



ITER



Detailed Design Has Been Developed



- Central Solenoid**
Nb₃Sn, 6 modules
- PoIoidal Field Coil**
Nb-Ti, 6
- Toroidal Field Coil**
Nb₃Sn, 18, wedged
- Blanket Module**
440 modules
- Port Plug**
heating/current drive
test blankets
limiters/RH
diagnostics
- Divertor**
54 cassettes
- Torus Cryopump**
8 units
- Vacuum Vessel**
9 sectors
- Cryostat**
24 m high x 28 m dia.

Fusion Power: 500 MW
Plasma Volume: 840 m³
Plasma Current: 15 MA
Typical Density: 10²⁰ m⁻³
Typical Temperature: 20 keV

ITER



MINISTERIO DE EDUCACIÓN Y CIENCIA

ITER CHALLENGES

LARGE TECHNOLOGY DEVELOPMENT

CENTRAL SOLENOID MODEL COIL

Completed R&D Activities by July 2001

Radius 3.5 m
Height 2.8m
 $R_{\text{coil}} = 13.1$
W = 640 MJ
0.6 T/m

VACUUM VESSEL SECTOR

Double-Wall, Tolerance ± 0.5 mm

High Joining Tech
Size: 1.6 m x 0.93 m x 0.35 m

REMOTE MAINTENANCE OF DIVERTOR CASSETTE

Attachment Tolerance ± 2 mm

DIVERTOR CASSETTE

Height 4 m
Width 3 m
 $B_{\text{coil}} = 1.8$ T
 $I_{\text{coil}} = 80$ kA

TOROIDAL FIELD MODEL COIL

4 (Blanket) Sector
Attachment Tolerance ± 0.25 mm



The New York Times

Vol. LXXXV, No. 46,081 NEW YORK, FRIDAY, NOVEMBER 22, 1985

Text of the Joint U.S.-Soviet Statement: 'Greater Understanding Achieved'

Fusion Research

The two leaders emphasized the potential importance of the work aimed at utilizing controlled thermonuclear fusion for peaceful purposes and, in this connection, advocated the widest practicable development of international cooperation in obtaining this source of energy, which is essentially inexhaustible, for the benefit for all mankind.



Broadening the Scope of ITER

- Suggested initially to resolve ITER siting problem.
- Includes:
 - Remote experimental control centre as focus for interaction with ITER.
 - Virtual plasma modelling laboratory to bring together models for plasma behaviour on ITER and to make predictions, feeding back information subsequently from ITER operation.
 - “Satellite” tokamak providing support (and ability to rapidly evaluate new ideas) during ITER construction and operation.
 - DEMO design team.
 - DEMO materials test/qualification facility (IFMIF).
- Implementation details now being discussed between Europe and Japan.

December 6, 2005

ITER

Negotiations

- Began in July 2001 with the following aims:
 - draft Joint Implementation Agreement agree how the procurement and costs will be shared define how the project will be managed
 - ⇒ Schedule foresees Agreement initialling in January-March 2006.
 - ⇒ India possibly joining adds further complexity.
 - ⇒ Signature/ratification by end of 2006 foreseen.
 - select ITER construction site
 - ⇒ Cadarache site chosen in June 2005.
 - ⇒ Cadarache Joint Work Site starts January 2006.
 - identify the Director General and senior staff.
 - ⇒ Kaname Ikeda chosen as DG in November 2005.
 - ⇒ Principal Deputy to be chosen by Europe soon.
 - ⇒ DG + PD to draft Project Team details.



December 6, 2005

ITER

Construction Cost Sharing

CN/KO/RF/US		ITER Construction		Complementary Programme
		10% each total	40%	
EU + JA	Host of ITER Facility	≤ 50%	?	≤ 8%
	Host of Complementary Programme	≥ 10%	?	≤ 8%
Sum		100%*	?	≤ 16% + ?

*90% in kind, 10% in cash from shared funds;

*Allocation of 80% of procurements have already been tentatively agreed.

*Situation prior to Interest of India to participate.

December 6, 2005

ITER

• CN: magnet support, feeders, correction coils, conductors, blanket (0.2), cryostat gas injection, casks (0.5), HV substation, AC/DC (0.35), diag.
 • EU: TF(0.5), conductors, cassette and outer target, vac pumps, div. RH, cask (0.5), isotope sep., IC, EC, diag.
 • JA: TF(0.5), conductors, inner target, blanket RH, EC, diag.
 • KO: conductors, vessel ports (0.57), blanket (0.2), assembly tools, thermal shield, storage, AC/DC (0.65), diag.
 • RF: PF1, conductors, vessel ports (0.33), blanket (0.2), port limiters, nozzles, dome and PFC tests, Discharge circuits, EC, diag.
 • US: CS(0.5), conductors, blanket (0.1), vac pumps, pellet inlets, vessel-vessel cooling, tok ext. proc., IC, EC, diag.

Risk Management - The Problem

- 90% of items will be provided in kind from the 6 Parties and sharing amongst them has not been optimised especially to minimise risk.
- Such an experiment cannot be built without some changes during construction which may affect suppliers in several Parties.
- Unlike normal centrally-funded projects, any margins actually realised will not be seen by the project for items provided in kind.
- The project therefore has no “cushion” for overcost items or failed/delayed deliveries.
- Very long time scale of the project and lack of experts.

December 6, 2005

ITER

Large Number of Specific Very High Quality Components

500 t of Nb₃Sn, 2000 first wall panels and 2000 divertor elements

- Risks:
 - Too low production/acceptance rate.
 - Too high costs.
- Minimisation of risks:
 - R&D including QA.
 - Qualification of potential vendors before call for tender. (Nb₃Sn strands: Trial production and tests ongoing with 15 vendors) (First wall panel: Trial production and tests will start soon)
 - Fixed price contracts with multiple vendors with demonstrated capability.
 - Staged production and “holding” of cash contingency.
- Mitigation of consequences:
 - Transfer of remaining production to other vendors demonstrating adequate production quality. A solution is needed for funds transfer from the defaulting to the compensating Party.

December 6, 2005

ITER

Large and Complex Tokamak Core Components

- Risks:
 - Unacceptable delays.
 - Inability to maintain quality in series production.
 - Design changes.
 - Too high costs.
- Minimisation of risks:
 - R&D (7 Large Projects), detailed fabrication and QA (in progress).
 - Very good preparation esp. specification and planning (underway).
 - Firm and fixed price contracts for reasonably large packages of work.
 - Prime - subcontractor relationship between multiple Parties' vendors.
 - Very good direct relationship between ITER International Organisation and vendors.
- Mitigation of consequences:
 - ITER International Organisation must minimise cost impact of changes.
 - ITER International Organisation must seek compensating cost savings within the contract, or with other contracts.
 - Access to a general reserve fund as a last resort.

December 6, 2005

ITER

Complex Organization and Lack of Experts

Risks


- Lack of specialists.
- Lack of technical continuity due to long time scale
 - » retirement of senior staff in IT, PTs and Industry who actively participated from the beginning of the ITER Engineering Design Activities in the early 1990s.
- Inefficiency of complex international structure.

December 6, 2005

ITER

Roles and Responsibilities: The Parties

Can they be simultaneously stakeholders and suppliers?.




December 6, 2005

ITER

Simple Relation between ITER Organization (via Branch Office) & Supplier

Parties' Agencies must play a supporting rather than a leading role.

Component procured by Party A



Component shared by Party A and Party B



Extremely inefficient arrangement for a core component shared by multi Parties.




December 6, 2005

ITER

Example Solution to Risk Sharing Between Project and Parties

In-kind contribution, before contract placement




After contract placement



December 6, 2005

ITER

Improvement of Configuration Management Tools




- Complexity, clash detection, utility routing, collaborative design with Participants, need better tools.
- ITER needs "Virtual product data management" software for 3D digital mockup. Implemented in 2004, upgraded at end of 2005.
- Complete switch to CATIA V5 at end of 2004.

December 6, 2005

ITER

Remote Participation in ITER Experimentation

Efficient Use of ITER
Involvement of Worldwide Community



December 6, 2005

ITER


Conclusions

- The ITER Transitional Arrangements are being used at the project technical level to get many things ready that will ease the path once the negotiations are successfully completed.
- Further careful considerations and preparations are required, especially in the **Project Organization, Staffing, Procurement System, and the relationship among the ITER International Organization, Domestic Agencies and suppliers.**
- Joint implementation Agreement** should leave enough **flexibility** for the Project's Director-General.
- Following the site decision, progress now being made on all fronts, with **ITER and Broader Approach** items. Lack of decision on the site has set the **date of first plasma back 2 years, to 2016.**
- The **success of ITER will require the strongest commitment** of all the **Parties** and their **industries** to provide the specified components at the required quality level and on schedule.

December 6, 2005

ITER


Immediate Schedule



December 6, 2005

ITER

Construction Schedule



December 6, 2005

ITER